

4.10 BOP Handling Unit

TFI BOP handling unit is integrated with a fully hydraulic control assembly to lift BOPs. It is explosion proof, easy to operate and maintain and has excellent reliability.

Model	Max. Lifting Capacity	Max. Lifting Height	Max. Lifting Speed	Max. Lowering Speed	Max. Horizontal Moving Speed	Hydraulic System Max. Working Pressure	Hydraulic System Max. Flow Rate
	kN (lbs)	m (ft)	m/min (in/min)	m/min (in/min)	m/min (in/min)	MPa (psi)	L/min (gal./min)
DZ400	400 (89,923)	3.2 (10')	1.6 (63)	3.3 (130)	12 (472)	16 (2320)	80 (21)
DZ500	500 (112,404)	3.2 (10')	1.6 (63)	3.3 (130)	12 (472)	16 (2320)	80 (21)
DZ550	550 (123,644)	3.2 (10')	1.6 (63)	3.3 (130)	12 (472)	17.5 (2538)	80 (21)